

Takeoff Tab

Masonry Estimate Sample Project

Bid No. 34

No.	Name	Height	Area	Quantity1 UOM1	Quantity2 UOM2	Quantity3 UOM3
Exterior finish						
12	face brick	0"	(unassigned)	34,900 SF	12,459 LF	0
13	Stone Veneer	0"	(unassigned)	3,021 SF	1,409 LF	0
EXTERNAL CMU WALL						
1	4/A6.5 WS - S21 -BR -INS-12"CMU @ ELEV	30' 0"	(unassigned)	32 LF	5 EA	0
3	4/A6.4 WS - S21 -BR -INS-12"CMU @ KITCHEN	21' 0"	(unassigned)	128 LF	2 EA	0
6	3/A6.2 WS - S7 - ST - INS-12" CMU @ ART	22' 0"	(unassigned)	20 LF	2 EA	0
7	4/A6.2 WS - S8 - ST - INS-12" CMU @ ART WINDOW SEAT	22' 0"	(unassigned)	19 LF	3 EA	0
8	1/A6.2 WS - S9 - ST - INS-12" CMU @ ART SEAT WALL	10' 6"	(unassigned)	14 LF	4 EA	0
Interior Walls						
4	C12 @ 15'7"	15' 7"	(unassigned)	444 LF	7 EA	0
5	C8 @ 15'7"	15' 7"	(unassigned)	97 LF	7 EA	0
Lintel						
10	Lintel 3' Dept 0'-8" Top Reinforcement - - Bottom Reinforcement - (2)-#5 Vertical Lintel Reinforcement For Lintels - #4 at 1'-0" OC	0"	(unassigned)	24 LF	7 EA	0
9	Lintel 7' Dept 1'-4" Top Reinforcement - (2)-#5 Bottom Reinforcement - (2)-#5 Vertical Lintel Reinforcement For Lintels - #4 at 1'-0" OC	0"	(unassigned)	30 LF	5 EA	0
11	Lintel 12' Dept 2'-0" Top Reinforcement - (2)-#5 Bottom Reinforcement - (2)-#5 Vertical Lintel Reinforcement For Lintels - #4 at 1'-0" OC	0"	(unassigned)	25 LF	2 EA	0
Marker						
2	Marker tool	0"	(unassigned)	2 EA	0	0